

# Municipal City Council of Port Louis

## Award of Procurement Contract

### Notice under section 40(7) of the Public Procurement Act

This is to notify that, following the bidding exercise carried out by the Municipal City Council of Port Louis for the Resurfacing of Roads, Construction of New roads and related Works (ONB/CCPL/004/17), the contract has been awarded to J.Dookun & Sons Ltd which is as follows:

| Item | Description   | Unit           | Price (VAT Inclusive) |
|------|---|----------------|-----------------------|
| 1    | (a) Cleaning of road surface, removal of loose materials and cart away  | m <sup>2</sup> | 5.00                  |
|      | (b) Weeding and cart away (if away)   | m <sup>2</sup> | 5.00                  |
| 2    | Scarification : Scarifying, loosening and digging of any material from carriageway, shoulder, verge including top soil, demolition of existing concrete kerbs or wall and any features bordering the carriageway, loading and cart away. Works will also include shaping and compaction of the bottom of excavation to 95% B.S. Heavy compaction or as directed by Engineer and any miscellaneous works arising | m <sup>3</sup> | 400.00                |
| 3    | Excavation (in any materials) & cart away   | m <sup>3</sup> | 300.00                |
| 4    | Fill with materials from excavation   | m <sup>3</sup> | 75.00                 |
| 5    | Levelling of depressions with crusher run - 0/20 prior to reshapingf and for base course. Works will involve Supply, Lay & Compact crusher run-0/20 as per specifications   | m <sup>3</sup> | 1,560.00              |
| 6    | Supply and Application /Spray Prime Coat 1.2 L/m <sup>2</sup>   | m <sup>2</sup> | 35.00                 |
| 7    | Cut Asphalt using asphalt cutter or as approved by the Engineer at straight edge and Patch with Bituminous concrete (0/10), minimum thickness of 50 m.m   | m <sup>2</sup> | 680.00                |
| 8    | Milling of Asphalt concrete   | m <sup>3</sup> | 3,100.00              |
| 9    | Supply and Application of Tack Coat MC30 cut back bitumen at the rate of 0.6 Kg/m <sup>2</sup>  | m <sup>2</sup> | 35.00                 |

|    |  |                |          |
|----|--|----------------|----------|
| 10 | Reshaping or Wearing course or Base course as specified -<br>Provide, lay & Roll Hot Premixed Bituminous concrete<br>Asphalt - 0/14  | m <sup>3</sup> | 8,700.00 |
| 11 | Road marking - Hot Melt Thermoplastic type   | m <sup>2</sup> | 600.00   |
| 12 | Supply and transport to site & Lay Hot Premixed Bituminous<br>Asphaltic concrete 0/10 according to specifications.<br>Application of 40 mm thick (minimum thickness after<br>compaction) Hot Premixed Bituminous Asphaltic concrete 0/10<br>including compacting and leveling for any width & trimming of<br>edges | m <sup>2</sup> | 630.00   |

|    |  |  |  |
|----|--|--|--|
| 13 | Raising manholes (various dimensions)<br>≤ 500 x 500 mm<br>> 500 x 500 mm  | Unit<br>Unit   | 2,000.00<br>2,500.00   |
| 14 | Raising of Drains/ Cross Drains & Reinstatement etc. Works to<br>include Concrete kerbs (on mass concrete) of dimensions n.e<br>200 x 330 mm (reinf: 4Y10/R6-250) with concrete mix class<br>25, hacking of concrete, dowelling as per site instruction<br><br>- Open drain (both borders inclusive)<br>- Covered drain including RC slabs and metal grating (both<br>borders inclusive)   | m<br>m   | 600.00<br>1,000.00   |
| 15 | Felling of trees Girth - 300 - 600 mm<br><br>Felling of trees Girth - above 600 mm   | Unit   | 1,500.00<br>2,000.00   |
| 16 | Associated works<br>(a) Supply and place & compact concrete<br>- Grade 15 concrete (mass)<br>- Grade 25 structural concrete<br>- Grade 30 structural concrete<br><br>(b) Formwork: Supply and fixing (including striking off)<br>(c) Reinforcement: Supply and fixing<br>(d) Supply, lay & compact crusher run 0/31.5<br>(e) Spalls: Supply, lay (size 100-200) & compact<br><br>(f) Geotextile: supply and fix as per specifications) | m <sup>3</sup><br>m <sup>3</sup><br>m <sup>3</sup><br>m <sup>2</sup><br>Kg<br>m <sup>3</sup><br>m <sup>3</sup><br>m <sup>2</sup> | 3,500.00<br>4,100.00<br>4,300.00<br>250.00<br>46.00<br>1,560.00<br>1,500.00<br>75.00 |

|  |   |        |
|--|---|--------|
| (g) Precast or cast in situ concrete kerks as per drawings |   |        |
| Type K1  | m | 525.00 |
| Type K2  | m | 525.00 |
| Type K3  | m | 525.00 |
| Type K4  | m | 525.00 |



J. Mulloo  
Chief Executive