



THE MUNICIPAL CITY COUNCIL OF PORT-LOUIS

AWARD OF PROCUREMENT CONTRACT

Notice under Section 40(7) of the Public Procurement Act

This is to notify that, following the bidding exercise carried out by the Municipal City Council of Port Louis for Resurfacing of Roads, Construction of New Roads and Related Works within the City Council of Port Louis (ONB/CCPL/009/18-19), the contract has been awarded to *J.Dookhun & sons Ltd* of *Royal Road, Petite Riviere* as per the rates at annex.


J.Mulloo

Chief Executive

16 July 2019

Annex

| SCHEDULE OF RATES | | | |
|--|--|----------------|-------------------------|
| Supply, Lay & Compact Hot Premixed Bituminous Asphalt and Related Works | | | Rates |
| S /N | Description | Unit | Incl of VAT (Rs) |
| 1 | (a) Cleaning of road surface, removal of loose materials and cart away | m ² | 5.00 |
| | (b) Weeding and cart away (if any) | m ² | 5.00 |
| 2 | Scarification : Scarifying, loosening and digging of any material from carriageway, shoulder, verge including topsoil, demolition of existing concrete kerbs or wall and any features bordering the carriageway, loading and cart away. Works will also include shaping and compaction of the bottom of excavation to 95% B.S. Heavy compaction or as directed by Engineer and any miscellaneous works arising | m ³ | 100.00 |
| 3 | Excavation (in any materials) and cart away | m ³ | 100.00 |
| 4 | Fill with materials from excavation | m ³ | 20.00 |
| 5 | Leveling of depressions with crusher run - 0/20 prior to reshaping and for base course. Works will involve Supply, Lay & Compact crusher run - 0/20 as per specifications | m ³ | 1,500.00 |
| 6 | Supply & Application /Spray Prime Coat 1.2 L/m ² | m ² | 25.00 |
| 7 | Cut Asphalt using asphalt cutter or as approved by the Engineer at straight edge and Patch with Bituminous concrete (0/10), minimum thickness of 50 mm | m ² | 500.00 |
| 8 | Milling of Asphalt Concrete | m ³ | 2,500.00 |
| 9 | Supply & Application /Spray Tack Coat MC30 cut back bitumen at the rate of 0.6 Kg/m ² | m ² | 30.00 |
| 10 | Reshaping or Wearing course or Base course as specified - provide, lay & Roll Hot Premixed Bituminous Concrete Asphalt - 0/14 | m ³ | 2,500.00 |
| 11 | Road Marking - Hot Melt Thermoplastic Type | m ² | 500.00 |
| 12 | Supply & transport to site & Lay Hot Premixed Bituminous Asphaltic concrete 0/10 according to specifications. Application of 40 mm thick (average thickness after compaction) Hot Premixed Bituminous Asphaltic concrete 0/10 including compacting and leveling for any width & trimming of edges. | m ² | 750.00 |
| 13 | <u>Raising manholes (various dimensions)</u> | | |
| | ≤ 500 x 500 mm | Unit | 500.00 |
| | > 500 x 500 mm | Unit | 800.00 |

| | | | |
|---------|---|----------------|----------|
| 14 | Raising of Drains/ Cross Drains & Reinstatement etc . Works to include Cast in-situ Concrete kerbs (on mass concrete) of dimensions n.e. 200 x 330 mm (reinft: 4Y10/R6-250) with concrete mix class 25. hacking of concrete, dowelling as per site instruction | | |
| | - Open drain (both borders inclusive) | m | 800.00 |
| | - Covered drain including RC slabs and metal gratings (both borders inclusive) | m | 1,000.00 |
| 15 | Felling of Trees Girth - 300 - 600 mm | unit | 300.00 |
| | Felling of Trees Girth - Above 600 mm | unit | 500.00 |
| 16 | Associated Works | | |
| | (a) Supply and place & compact concrete (m ³) | | |
| | - grade 15 concrete (mass) | m ³ | 3,000.00 |
| | - grade 25 structural concrete | m ³ | 4,000.00 |
| | - grade 30 structural concrete | m ³ | 4,200.00 |
| | (b) Formwork: Supply & fixing formwork (including striking off) | m ² | 125.00 |
| | (c) Reinforcement: Supply and fixing | kg | 45.00 |
| | (d) Supply, lay & compact crusherun 0/31.5 | m ³ | 1,500.00 |
| | (e) Spalls: Supply, lay (size: 100-200) & compact | m ³ | 1,200.00 |
| | (f) Geotextile: Supply & fix as per specifications | m ² | 50.00 |
| | (g) Precast or cast in situ concrete kerbs as per drawings | | |
| Type K1 | m | 500.00 | |
| Type K2 | m | 500.00 | |
| Type K3 | m | 500.00 | |
| Type K4 | m | 500.00 | |