



MUNICIPAL COUNCIL OF PORT LOUIS

NOTICE

Resurfacing of Roads, Construction of New Roads & Related Works within the boundaries of Port- Louis

Bid No: ONB/CCPL/003/18-19

Five Bids were opened on 01st October 2018 which is as follows:

Schedule of Rates

S. No		Description	Unit	Rate (inclusive of VAT)MUR				
				J.Dookun & Sons Ltd	Gamma Construction Ltd	Best Care Ltd	Safety Construction Co Ltd	Transinvest Construction Ltd
1		(a) Cleaning of road surface, removal of loose materials and cart away	m ²	5	18.29	20	162	50.60
		(b) weeding and cart away (if any)	m ²	5	18.29	20	162	16.10
2		Scarification: Scarifying, loosening and digging of any material from carriageway, shoulder, verge including topsoil, demolition of existing concrete kerbs or wall and any features bordering the carriageway, loading and cart away. Works will also include shaping and compaction of the bottom of	m ³	200	573.85	400	1,043	545.10

ok Mer 18

	excavation to 95% B.S. Heavy compaction or as directed by Engineer and any miscellaneous works arising.											
3	Excavation (in any materials) and cart away	m ³	200	528.89	300	1,202	545.10					
4	Fill with materials from excavation	m ³	30	234.37	250	359	423.20					
5	Leveling of depressions with crusher run- 0/20 prior to reshaping and for base course. Works will involve Supply, Lay & compact crusher run- 0/20 as per specifications.	m ³	1560	2,329.44	1,300	2,460	3,179.75					
6	Supply & Application/Spray Prime Coat 1.2L/m ²	m ²	30	47.84	20	135	86.25					
7	Cut Asphalt using asphalt cutter or as approved by the Engineer at straight edge and Patch with Bituminous concrete (0/10), minimum thickness of 50 mm	m ²	600	242.65	50	1,579	741.75					
8	Milling of Asphalt concrete	m ³	1,800	1,891.29	3,000	3,481	4,506.85					
9	Supply & Application/Spray Tack Coat MC30 cut back bitumen at the rate of 0.6 Kg/m ²	m ²	30	27.03	20	40	41.40					
10	Reshaping or Wearing course or Base course as specified - Provide, lay & Roll Hot Premixed Bituminous Concrete Asphalt-0/14.	m ³	3,000	14,028.28	8,000	17,581	16,503.75					
11	Road marking-Hot Melt Thermoplastic type	m ²	200	990.15	400	944	734.85					
12	Supply & transport to site & Lay Hot Premixed Bituminous Asphaltic concrete 0/10 according to specifications Application of 40mm thick (minimum thickness after compaction)Hot	m ²	690	544.53	500	704	602.60					

em/10/19

	Premixed Bituminous Asphaltic concrete 0/10 including compacting and leveling for any width & trimming of edges								
13	Raising manholes (various dimensions) ≤ 500 x 500 mm > 500 x 500 mm	Unit Unit	800 1,000	4,304.80 6,026.69	1,500 1,500	6,997 15,429	7,797 7,797		
14	Raising of Drains/Cross Drains & Reinstatement etc. Works to include Cast in-situ Concrete kerbs (on mass concrete) of dimensions n.e. 200 x 330mm (reinf: 4Y10/ R6-250) with concrete mix class 25, hacking of concrete, dowelling as per site instruction. - Open drain (both borders inclusive) - Covered drain including RC slabs and metal grating (both borders inclusive)	m m	600 800	1,023.73 2,175.69	500 600	4,602 6,817	4,129.75 4,129.75		
15	Felling of Trees Girth- 300-600 mm Felling of Trees Girth- Above 600 mm	unit unit	500 800	7,393.47 9,545.81	1,700 1,700	12,558 16,146	10,396 16,459		

07/10/18

Type K2	m	500	769.58	200	897	952.20
Type K3	m	500	852.04	300	736	955.65
Type K4						

02 October 2018

er/10/18